


versatile™ 4C Mailbox, 4CADS-01



COMPARTMENT CHART

| DESCRIPTION | COMPARTMENT | COMPARTMENT SIZE | QTY. |
|---------------|-------------|---------------------------|------|
| MAILBOX | MB2 | 6-1/2" H x 12" W x 15" D | 1 |
| OUTGOING MAIL | OM2 | 6-1/2" H x 12" W x 15" D | 1 |
| PARCEL | PL6 | 20-1/2" H x 12" W x 15" D | 1 |

- Notes:**
- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
 - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - No patron (tenant) lock shall be positioned more than 67" AFF.
 - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - The USPS Arrow lock shall be positioned 36"- 48" AFF.
 - This 4C mailbox can also be used for private applications.
 - The rough opening width for multi-unit 4C installations is provided using the Florence configurator: www.florencemailboxes.com/configurator.

| | | | |
|--|----------|---------------|----------|
| PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX | | | |
| MODEL | 4CADS-01 | REV | B |
| SCALE | NONE | LAST REV DATE | 06/29/19 |
| DRAWING NUMBER | | DRAWN BY | |
| 4CADS-01CS | | RAK | |